

# WESTERN SUSSEX BUSINESS CAMPUS

#### SITE DATA OWNER OF RECORD: 205 CANNON STREET CHESTERTOWN, MD 21620

ENGINEER / SURVEYOR: BECKER MORGAN GROUP INC 309 S GOVERNORS AVENUE DOVER, DE 19904

PROPERTY MAP NUMBER 331-5.00-4.29 ZONING CLASSIFICATION: EXISTING: M-1 - LIGHT INDUSTRIA

M-1 - LIGHT INDUSTRIAL DEED SUMMARY PLAT REFERENCE

PROPOSED USE OFFICE FLEX / MANUFACTURING TOTAL SITE AREA: PROPOSED BUILDING IMPERVIOUS COVERAGE: PROPOSED: 339,446 S.F. (7.79 ACRES

1 SPACE FOR EVERY 1000 S.F. OF GFA

VACANT LAND

140 000 S F / 1 000 S F = 140 PARKING SPACES PROVIDED: 192 PARKING SPACES PROVIDED HANDICAP PARKING SPACES: 16

LOADING BERTHS: 1 SPACE FOR AND COMMERCIAL OR INDUSTRIAL OVER

PROVIDED: 27 13. SETBACKS M-1 - LIGHT INDUSTRIAL

SIDE: 25 FT. 15 FT. REAR: 14. LOT SIZE: 2 AC. MIN.

PRESENT USE:

2. PARKING CALCULATIONS:

1 SPACE FOR EVERY 1000 S.E. OF GEA LANDSCAPE REQUIREMENT 210.000 S.F. / 1.000 S.F. = 210 PARKING SPACES

SIGNAGE

7. LOT COVERAGE: PROPOSED: 20% 140.000 S.F. / 716.126.40 S.F. = 20% 8. PAVED AREA COVERAGE: PERMITTED: 30% 716,126.40 S.F. \* 0.30 = 214,938 S.F.

BUILDING HEIGHT O. SOURCE OF WATER: CITY OF SEAFORD 21. SOURCE OF SEWER: CITY OF SEAFORD 22. SOURCE OF GAS: CHESAPEAKE UTILITIES

23. SOURCE OF ELECTRIC: CITY OF SEAFORD 24. TOTAL WETLAND AREA: 0.00 AC.

#### SEDIMENT AND STORMWATER CONSTRUCTION NOTES:

CONSTRUCTION. FAILURE TO DO SO CONSTITUTES A VIOLATION OF THE APPROVED SEDIMENT AND STORMWATER

PROPOSED: 28% 201,246 S.F. / 716,126.40 S.F. = 28%

- REVIEW AND OR APPROVAL OF THE SEDIMENT AND STORMWATER MANAGEMENT PLAN SHALL NOT RELIEVE THE CONTRACTOR FROM HIS OR HER RESPONSIBILITIES FOR COMPLIANCE WITH THE REQUIREMENTS OF THE DELAWARE SEDIMENT AND STORMWATER REGULATIONS, NOR SHALL IT RELIEVE THE CONTRACTOR FROM ERRORS OR OMISSIONS IN THE APPROVED
- IF THE APPROVED PLAN NEEDS TO MODIFIED. ADDITIONAL SEDIMENT AND STORMWATER CONTROL MEASURES MAY B REQUIRED AS DEEMED NECESSARY BY SCD / DNREC
- FOLLOWING SOIL DISTURBANCE OR RE-DISTURBANCE, PERMANENT OR TEMPORARY STABILIZATION SHALL BE COMPLETED FOR ALL PERIMETER SEDIMENT CONTROLS, SOIL STOCKPILES, AND ALL OTHER DISTURBED OR GRADED AREAS ON THE PROJECT SITE WITHIN FOURTEEN (14) CALENDAR DAYS LINEESS MORE RESTRICTIVE FEDERAL REQUIREMENTS APPLY
- AT ANY TIME A DEWATERING OPERATION IS USED, IT SHALL BE PREVIOUSLY APPROVED BY THE AGENCY CONSTRUCTION SITE REVIEWER FOR A NON-EROSIVE POINT OF DISCHARGE, AND A DEWATERING PERMIT SHOULD BE APPROVED BY THE DNREC WELL PERMITTING BRANCH.
- POST CONSTRUCTION VERIFICATION DOCUMENTS SHALL BE SUBMITTED TO THE SUSSEX CONSERVATION DISTRICT SEDIMENT AND STORMWATER PROGRAM WITHIN 60-DAYS OF STORMWATER MANAGEMENT FACILITY COMPLETION
- APPROVAL OF A SEDIMENT AND STORMWATER MANAGEMENT PLAN DOES NOT GRANT OR IMPLY A RIGHT TO DISCHARGE STORM WATER RUNOFF. THE OWNER/DEVELOPER IS RESPONSIBLE FOR ACQUIRING ANY AND ALL AGREEMENTS, EASEMENTS ETC., NECESSARY TO COMPLY WITH STATE DRAINAGE AND OTHER APPLICABLE LAWS.
- THE NOTICE OF INTENT FOR STORMWATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITY UNDER A NPDES GENERAL PERMIT FOR THIS PROJECT IS #6884. T ANY TIME THE OWNERSHIP FOR THIS PROJECT CHANGES, A TRANSFER OF AUTHORIZATION OR A CO-PERMITTEE APPLICATION MUST BE SUBMITTED TO DNREC. THE PERMITTEE OF RECORD SHALL NOT BE RELIEVED OF THEIR RESPONSIBILITY UNTIL A NOTICE OF TERMINATION HAS BEEN PROCESSED BY DNREC
- THE OWNER SHALL BE FAMILIAR WITH AND COMPLY WITH ALL ASPECTS OF THE NPDES CONSTRUCTION GENERAL PERMIT ASSOCIATED WITH THE PROJECT, INCLUDING BUT NOT LIMITED TO, PERFORMING WEEKLY SITE INSPECTIONS DURING
- CONSTRUCTION AND AFTER RAIN EVENTS. AND MAINTAINING WRITTEN LOGS OF THESE INSPECTIONS THE CONTRACTOR SHALL AT ALL TIMES PROTECT AGAINST SEDIMENT OR DEBRIS LADEN RUNOFF OR WIND FROM LEAVING THE SITE. PERIMETER CONTROLS SHALL BE CHECKED DAILY AND ADJUSTED AND/OR REPAIRED TO FULLY CONTAIN AND CONTROL SEDIMENT FROM LEAVING THE SITE. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT HAS REACHED HALF OF THE EFFECTIVE CAPACITY OF THE CONTROL. IN ADDITION, THE CONTRACTOR MAY NEED TO ADJUST OR ALTER MEASURES. IN TIMES OF ADVERSE WEATHER CONDITIONS, OR AS DIRECTED BY THE AGENCY CONSTRUCTION SITE REVIEWER
- BEFORE ANY EARTHWORK OR EXCAVATION TAKES PLACE THE CONTRACTOR SHOULD CALL MISS UTILITY AT 811 OR 1-800-282-8555 AT LEAST 48 HOURS PRIOR TO CONSTRUCTION, TO HAVE ALL EXISTING UTILITY MARKED ONSITE.
- BEST AVAILABLE TECHNOLOGY (BAT) SHALL BE EMPLOYED TO MANAGE TURBID DISCHARGES IN ACCORDANCE WITH REQUIREMENTS OF 7. DEL C. CH60, AND THE CURRENT DELAWARE CONSTRUCTION GENERAL PERMIT (CGP).
- DOCUMENTATION OF SOIL TESTING AND MATERIALS USED FOR TEMPORARY OR PERMANENT STABILIZATION INCLUDING BUT NOT LIMITED TO SOIL TEST RESULTS, SEED TAGS, SOIL AMENDMENT TAGS, ETC. SHALL BE PROVIDED TO THE SUSSEX CONSERVATION DISTRICT / DNREC TO VERIFY THAT THE PERMANENT OR TEMPORARY STABILIZATION HAS BEEN COMPLETED IN ACCORDANCE WITH THE APPROVED PLAN.
- THE SUSSEX CONSERVATION DISTRICT / DNREC MAY REQUIRE ADDITIONAL SOIL TESTING AND REAPPLICATION OF PERMANEN' OR TEMPORARY STABILIZATION IN ACCORDANCE WITH SPECIFICATIONS IN THE DELAWARE EROSION AND SEDIMENT CONTROL HANDBOOK, OR ALTERNATIVE MEASURES THAT PROVIDE FUNCTIONAL EQUIVALENCY.
- WHEN DIRECTED BY THE SUSSEX CONSERVATION DISTRICT / DNREC, THE OWNER SHALL ACQUIRE THE SERVICES OF A THIRD PARTY CERTIFIED CONSTRUCTION REVIEWER (CCR) TO PERFORM WEEKLY CONSTRUCTION REVIEWS. SEDIMENT AND
- . THE SUSSEX CONSERVATION DISTRICT / DNREC RESERVES THE RIGHT TO ENTER PRIVATE PROPERTY FOR PURPOSES OF

STORMWATER MANAGEMENT PLANS APPROVED BY THE DEPARTMENT SHALL HAVE A THIRD PARTY CCR.

- PERIODIC SITE INSPECTIONS. PERIODIC MAINTENANCE OF ALL SEDIMENT CONTROL MEASURES IS REQUIRED TO INSURE EFFECTIVE SEDIMENT CONTROL
- INSPECTION OF ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE MADE AT LEAST WEEKLY AND AFTER EACH RAINFALL EVENT. REPAIRS SHALL BE MADE WITHIN 24 HOURS OF THE RAIN EVENT OR WHEN OTHERWISE IDENTIFIED. THE SEQUENCE OF CONSTRUCTION ON THE APPROVED SEDIMENT AND STORMWATER MANAGEMENT PLAN MUST BE STRICTL' ADHERED TO. ANY DIVERGENCE FROM THE APPROVED CONSTRUCTION SEQUENCE REQUIRES A WRITTEN REQUEST TO
- . A COPY OF THE APPROVED SEDIMENT AND STORMWATER MANAGEMENT PLANS MUST BE MAINTAINED ON-SITE AT ALL TIMES . TO PREVENT OR REDUCE THE MOVEMENT OF DUST FROM DISTURBED SOIL SURFACES THE SITE SHALL BE SPRINKLED WITH
- WATER UNTIL THE SURFACE IS MOIST AND REPEATED AS NECESSARY. ALTERNATIVE METHODS OF DUST CONTROL REQUIRE B. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO MAINTAIN AND REPAIR ALL EROSION AND SEDIMENT CONTROL AND
- STORMWATER MANAGEMENT PRACTICES DURING UTILITY INSTALLATION. . THE CONTRACTOR IS RESPONSIBLE FOR MAINTENANCE OF ALL SEDIMENT AND EROSION CONTROL MEASURES DURING
- CONSTRUCTION.
- 5. ALL POINTS OF CONSTRUCTION INGRESS AND EGRESS SHALL BE PROTECTED TO PREVENT TRACKING OF MUD ONTO PUBLIC WAYS BY A STABILIZED CONSTRUCTION ENTRANCE. 6. A PRE-CONSTRUCTION MEETING MUST TAKE PLACE BEFORE ANY EARTH DISTURBING ACTIVITY BEGINS. THE MEETING MUST
- BE ATTENDED BY AN OWNER'S REPRESENTATIVE, CONTRACTOR, CCR (IF REQUIRED FOR THE SITE), AND DNREC INSPECTOR. SOIL STOCKPILE AREAS MUST BE DELINEATED. LOCATE STOCKPILES ON AREAS WITH LITTLE OR NO SLOPE. STOCKPILES MUST BE SURROUNDED WITH SILT FENCE OR A STABILIZED EARTHEN BERM. STOCKPILE AREAS MUST BE SEEDED WITH
- 8. SCD / DNREC RESERVES THE RIGHT TO WITHHOLD PERMITS AND LETTERS OF NO OBJECTION RELATED TO OBTAINING CERTIFICATES OF OCCUPANCY FROM THE LOCAL JURISDICTION FOR NON COMPLIANCE WITH THE PLANS AND SPECIFICATIONS FOR STORMWATER MANAGEMENT AND EROSION AND SEDIMENT CONTROL.
- 9. SCD / DNREC RESERVES THE RIGHT TO ADD, DELETE, MODIFY OR OTHERWISE ALTER THE SEDIMENT CONTROL PROVISIONS OF THIS PLAN IN THE EVENT ADDITIONAL PROTECTION BECOMES NECESSARY
- 30. EROSION AND SEDIMENT CONTROL WILL BE STRICTLY ENFORCED.

MODIFY AND THE WRITTEN APPROVAL OF SCD / DNREC.

- 31. SEDIMENT CONTROL FOR UTILITY CONSTRUCTION IN AREAS OUTSIDE OF DESIGNED CONTROLS:
- EXCAVATED TRENCH MATERIAL SHALL BE PLACED ON THE HIGH SIDE OF THE TRENCH.
- IMMEDIATELY FOLLOWING PIPE INSTALLATION THE TRENCH SHALL BE BACK FILLED. COMPACTED AND STABILIZED. TEMPORARY SILT FENCE OR STRAW BALE DIKES SHALL BE PLACED IMMEDIATELY DOWNSTREAM OF ANY DISTURBED AREA INTENDED TO REMAIN DISTURBED LONGER THAN ONE WORKING DAY.
- . EROSION CONTROL MATTING IS REQUIRED ON SLOPES OF 3:1 OR GREATER IN AREAS OF CONCENTRATED FLOW. MATTING
- TYPE IS TO BE BIO-DEGRAD NORTH AMERICAN GREEN S-150BN.(OR APPROVED EQUIVALENT) 2 ALL STORMWATER MANAGEMENT FACILITIES SHALL BE PRIVATELY OWNED, OPERATED, AND MAINTAINED

## SEDIMENT AND STORMWATER MANAGEMENT PLANS

NANTICOKE RIVER WATERSHED CITY OF SEAFORD SUSSEX COUNTY, DE 331-5.00-4.29

SHEET INDEX	
SHEET NO.:	TITLE:
C-500	COVER SHEET & GENERAL NOTES
C-501	PRE-CONSTRUCTION SITE STORMWATER MANAGEMENT PLAN
C-502	CONSTRUCTION SITE STORMWATER MANAGEMENT PLAN
C-503 - C-505	EROSION AND SEDIMENT CONTROL DETAIL SHEET

#### **OPERATION & MAINTENANCE NOTES**

- THE OWNER WILL BE RESPONSIBLE TO OPERATE AND MAINTAIN EACH POST CONSTRUCTION STORMWATER MANAGEMENT
- THE SCD SEDIMENT AND STORMWATER PROGRAM AND/OR THE DELEGATED AGENCY RESERVES THE RIGHT TO ENTER
- THE SCD SEDIMENT AND STORMWATER PROGRAM SHOULD BE NOTIFIED WITHIN 30 BUSINESS DAYS IF THE PROPERTY
- AGAINST ANY OWNER DEEMED NEGLIGENT IN FULFILLING THE OPERATION AND MAINTENANCE REQUIREMENTS OF THE
- DELAWARE SEDIMENT AND STORMWATER REGULATIONS.
- ANY DESIGN MODIFICATIONS MADE TO THE STORMWATER SYSTEM SHALL REQUIRED THE CREATION OF A NEW POST
- PLAN(S) BY THE SUSSEX CONSERVATION DISTRICT AND/OR THE DELEGATED AGENCY FOR ALL STORMWATER EASEMENTS AREAS AND THE MINIMUM 15FT WIDE ACCESSWAYS TO ALL STORMWATER FACILITIES
- 1-800-282-8555 AT LEAST 48 HOURS PRIOR TO CONSTRUCTION, TO HAVE ALL EXISTING UTILITIES MARKED ONSITE.
- THE MANAGER OF MAINTENANCE AND FACILITIES AND/OR OWNER SHOULD CONTRACT MANUFACTURE FOR THE LATEST
- SEDIMENT REMOVAL, PIPE INSPECTIONS, WATERING, RE-SEEDING/PLANTING, TRASH REMOVAL, ETC.

#### SEQUENCE OF CONSTRUCTION

TOTAL DISTURBED ACREAGE - 9.62 ACRES

- . NOTIFY SCD AT (302-856-2105) AND IN WRITING AT LEAST FIVE (5) DAYS PRIOR TO THE START OF CONSTRUCTION. FAILURE TO DO SO CONSTITUTES A VIOLATION OF THE APPROVED SEDIMENT AND STORMWATER MANAGEMENT PLANS. A CONSTRUCTION REVIEW IS REQUIRED AT THE PRE-CONSTRUCTION MEETING.
- PRIOR TO ANY CLEARING, INSTALLATION OF SEDIMENT CONTROL MEASURES OR GRADING, A PRE-CONSTRUCTION MEETING MUST BE SCHEDULED AND CONDUCTED WITH SCD. THE LANDOWNER/DEVELOPER. CONTRACTOR. GEO-TECH / SOIL SCIENTIST OF RECORD, AND THE THIRD PARTY CERTIFIED CONSTRUCTION REVIEWER (CCR) ARE REQUIRED TO BE IN ATTENDANCE AT THE PRE-CONSTRUCTION MEETING; THE DESIGNER IS RECOMMENDED TO ATTEND.
- OBTAIN ALL CITY, COUNTY, AND STATE PERMITS PRIOR TO THE START OF CONSTRUCTION
- 4. CLEAR AND GRUB AREAS NECESSARY FOR INSTALLATION OF PERIMETER CONTROLS. INCLUDING BUT NOT LIMITED TO: STABILIZED CONSTRUCTION ENTRANCE, SILT FENCE, AND INLET PROTECTION ON ALL EXISTING INLETS AND CULVERTS.
- INSTALL ALL PERIMETER CONTROLS AS SHOWN ON SHEETS C-501 AND C-502. ALL PERIMETER CONTROLS ARE TO BE REVIEWED BY THE DISTRICT SITE REVIEWER AND APPROVED PRIOR TO PROCEEDING WITH FURTHER SITE DISTURBANCE OR CONSTRUCTION. THE CONTRACTOR SHALL AT ALL TIMES PROTECT AGAINST SEDIMENT OR DEBRIS LADEN RUNOFF OR WIND FROM LEAVING THE SITE. PERIMETER CONTROLS SHOULD BE CHECKED DAILY AND ADJUSTED AND/OR REPAIRED TO FULL CONTAIN AND CONTROL SEDIMENTATION ON THE SITE. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT HAS REACHED HALF OF THE EFFECTIVE CAPACITY OF THE CONTROL. IN ADDITION, THE CONTRACTOR MAY NEED TO ADJUST OR REPAIR MEASURES IN TIMES OF ADVERSE WEATHER CONDITION, OR AS DIRECTED BY THE DISTRICT SITE REVIEWER.
- CLEAR AND GRUB VEGETATED AREAS NECESSARY FOR CONSTRUCTION. INSTALL SILT FENCE AROUND PROPOSED SOIL
- INSTALL UNDERGROUND UTILITIES INCLUDING ELECTRIC, TELEPHONE, CABLE, GAS, WATER, SEWER, AND STORM DRAINAGE. ABANDON/REMOVE EXISTING UTILITIES SERVICES FROM SITE. INSTALL INLET PROTECTION IN ALL CATCH BASINS PER PLAN. CONTACT UTILITY PROVIDERS, AS NECESSARY. INSTALL INLET PROTECTION ON ANY CATCH BASINS IMMEDIATELY AFTER
- 8. NOTIFY THE PERSON RESPONSIBLE FOR STORMWATER MANAGEMENT CONSTRUCTION REVIEW AT LEAST (3) DAYS PRIOR TO THE START OF CONSTRUCTION.
- 9. BULK GRADE SITE AREA. 10. BEGIN CONSTRUCTION OF BUILDING PAD AND STRUCTURES.
- 11. FINAL GRADE PROPOSED PAVED AREAS.
- 12. INSTALL CURB AND PAVEMENT STONE BASE AS SPECIFIED. 13. INSTALL TYPE "B" BINDER COURSE PER PAVEMENT SECTION.
- 14. INSTALL REMAINING SITE FEATURES (SIDEWALK, SIGNAGE, ETC.).
- 15. FINAL GRADE, TOPSOIL AND SEED THE REMAINING AREAS OF THE SITE PER SEEDING AND STABILIZATION NOTES. 16. INSTALL TYPE "C" PAVEMENT TOP COAT AND STRIPING.
- 17. EROSION AND SEDIMENT CONTROL DEVICES CAN BE REMOVED ONLY AFTER WORK IN THE AREA HAS BEEN STABILIZED, WITH
- 18. THE TERMINATION OF THE CONSTRUCTION GENERAL PERMIT WILL REQUIRE SUBMISSION AND ACCEPTANCE OF THE POST CONSTRUCTION VERIFICATION DOCUMENTS. INCLUDING FINAL STABILIZATION THROUGHOUT THE SITE. ALL ELEMENTS OF THE SEDIMENT AND STORMWATER MANAGEMENT PLAN IMPLEMENTED, AND ACCEPTANCE OF THE FINAL OPERATION AND MAINTENANCE PLAN. THE CONTRACTOR IS REQUIRED TO OBTAIN ANY INFORMATION NEEDED FOR THE PCVD.

#### STABILIZATION AND SEEDING NOTES

B. SEED BED PREPARATION: SHALL BE IN ACCORDANCE WITH DE-ESC-3.4.3, SHEET 4 OF 4.

B. APPLY MIX NO. 5 (ANNUAL RYEGRASS) IN ACCORDANCE WITH DETAIL DE-ESC-3.4.3, SHEET 1 OF 4.

FERTILIZER AND LIME APPLICATION SHALL BE IN ACCORDANCE WITH DE-ESC-3.4.3,

APPLY SEED UNIFORMLY WITH A BROADCAST SEEDER DRILL. CUI TIPACKER SEEDER OR

HYDROSEEDER. ALL SEED WILL BE APPLIED AT THE RECOMMENDED RATE AND PLANTING

IMMEDIATELY AFTER SEEDING, UNIFORMLY MULCH ENTIRE AREA WITH STRAW AT A RATE

P.E. NO. 18832 DATE

OF 2 TONS PER ACRE MINIMUM. ALL MULCHING SHALL BE DONE IN ACCORDANCE WITH

ALL AREAS TO BE PERMANENTLY SEEDED SHALL HAVE A MINIMUM OF 4" OF TOPSOIL.

- PERMANENT SEEDING A. SHALL BE CONDUCTED YEAR AROUND.
- PRIVATE PROPERTY FOR PURPOSES OF PERIODIC SITE REVIEWS.
- OWNERSHIP IS TRANSFERRED TO A NEW PERSON OR ENTITY.
- THE SCD SEDIMENT AND STORMWATER PROGRAM AND/OR THE DELEGATED AGENCY MAY SEEK ENFORCEMENT ACTION
- THE SCD SEDIMENT AND STORMWATER PROGRAM AND/OR THE DELEGATED SHOULD BE CONTACTED IF A CONCERN ARISES REGARDING A STORMWATER MANAGEMENT FACILITY. BEFORE ANY NON-ROUTINE MAINTENANCE, OR IF MODIFICATIONS TO
- CONSTRUCTION STORMWATER MANAGEMENT PLAN AND/OR OPERATION AND MAINTENANCE PLAN, WITH APPROVAL OF THE
- AND THEIR STRUCTURAL COMPONENTS. REGULAR MOWING SHOULD BE PERFORMED TO KEEP THE GRASS 6 INCHES OR LESS: NO TREES OR SHRUBS SHOULD BE PLANTED, AND ANY FOUND GROWING SHOULD BE REMOVED, AND NO PERMANENT
- STRUCTURES, SUCH AS FENCES OR SHEDS, SHOULD BE LOCATED WITH THE EASEMENT OR ACCESSWAY WHEN THE FACILITY IS EXCAVATED TO REMOVE ACCUMULATED SEDIMENT. THE DISPOSAL AREA SHALL BE PERMANENTLY STABILIZED SO THAT IS DOES NOT RECREATE AN EROSION PROBLEM. ANY MATERIAL TAKEN OFFSITE SHALL STILL BE USED OR DISPOSED OF IN AN APPROVED DNREC MANNER
- BEFORE ANY EARTH WORK OR EXCAVATION TAKES PLACE, THE CONTRACTOR SHOULD CALL MISS UTILITY AT 811 OR
- EDITION OF THE MAINTENANCE AND OPERATION MANUAL TO SUPPLEMENT THE MAINTENANCE ITEMS MENTIONED ABOVE.
- ANY FACILITY SPECIFIC ROUTINE OR NON-ROUTINE MAINTENANCE, AND/OR OPERATIONAL REQUIREMENTS NOT LISTED IN THE ABOVE-MENTIONED STANDARD REQUIREMENTS FOR THE TYPE OF FACILITY. MAY INCLUDE, BUT NOT LIMITED TO ANY MOWING

#### **ENGINEERS CERTIFICATION**

C. SOIL AMENDMENTS:

TEMPORARY STABILIZATION

C. MULCH SAME AS 1-E ABOVE

A. PROVIDE SEED BED SAME AS 1-B ABOVE.

COMPLETION OF GRADING OPERATIONS FOR THESE SLOPES.

E. MULCH:

F. TOPSOIL :

PHONE: 410.810.1574

I, JONATHAN D. RICHARD, HEREBY CERTIFY THAT DAM A REGISTERED ENGINEER IN THE STATE OF DELAWARE, THAT THE INFORMATION SHOWN HEREON HAS BEEN PREPARED VOLVER MY SUPERVISION AND TO MY BEST KNOWLEDGE AND BELIEF, REPRESENTS GOOD ENGINEERING RESECTIONS AS RECURSED BY THE APPLICABLE LAWS OF THE STATE OF DELAWARE.

IF TEMPORARY STABILIZATION IS REQUIRED, PERMANENT SEEDING SHALL BE PERFORMED AS SOON AS POSSIBLE.

ALL FILL SLOPE AREAS SHOWN ON PLAN ARE TO BE STABILIZED AS PER STATEMENT 1 OR 2 ABOVE IMMEDIATELY AFTER

EROSION CONTROL MATTING IS REQUIRED ON ALL SLOPES OF 3:1 OR GREATER AND IN AREAS OF CONCENTRATED FLOW.

DEPTH. IN ACCORDANCE WITH DE-ESC-3.4.3




#### OWNERS CERTIFICATION ONAL

, THE UNDERSIGNED CERTIFY THAT ALL LAND CLEARING, CONSTRUCTION AND DEVELOPMENT SHALL BE DONE PURSUANT TO THE APPROVED PLAN AND THAT RESPONSIBLE PERSONNEL (I.E., BLUE CARD HOLDER) INVOLVED IN THE LAND DISTURBANCE WILL HAVE A CERTIFICATION OF TRAINING PRIOR TO INITIATION OF THE PROJECT, AT A DNREC SPONSORED OR APPROVED TRAINING COURSE FOR THE CONTROL OF EROSION AND SEDIMENT DURING CONSTRUCTION. IN ADDITION, I GRANT THE DNREC SEDIMENT AND STORMWATER PROGRAM AND/OR THE RELEVANT DELEGATED AGENCY THE RIGHT TO CONDUCT ON-SITE REVIEWS. AND I UNDERSTAND MY RESPONSIBILITIES UNDER THE NPDES CONSTRUCTION GENERAL PERMIT, AS REFERENCED ON THIS COVERSHEET.

KRM DEVELOPMENT CORPORATION CHESTERTOWN, MD 21620

#### SEDIMENT AND STORMWATER APPROVAL STAMP

# **LOCATION MAP** SCALE: 1" = 800'



LO: LONGMARSH AND INDIANTOWN SOILS, FREQUENTLY FLOODED FadA: FALLSINGTON SANDY LOAMS, 0 TO 2 PERCENT SLOPES,

— L.O.D. –

PROPOSED

——12" W———

**──**○── **──**| **─** 

W.M. W.V.

<del>\_\_\_\_\_\_\_\_\_</del>\_\_\_

—— U.E.—— —

— — — U.T.— — —

——2" G———

HbA: HAMBROOK SANDY LOAM, 0 TO 2 PERCENT SLOPES

SadB: SASSAFRAS SANDY LOAM, 0 TO 2 PERCENT SLOPES,

**EROSION & SEDIMENT CONTROL LEGEND** 

LEGEND

**EXISTING** 

■EX. 10" F.M.

——EX. 10" W——

—∩— ——Ø⊦

W.M. W.V.

— — — —

- — — -U.T.- — -

—— EX. 2" G—— —

----49 ----

—— ——U.E.—— –

ImB: INGLESIDE HAMMONTON FALLSINGTON COMPLEX. 0 TO 9

NORTHERN TIDEWATER AREA

NORTHERN TIDEWATER AREA

STANDARD INLET PROTECTION - TYPE 1

STANDARD INLET PROTECTION - TYPE 2

STABILIZED CONSTRUCTION ENTRANCE

**CONCRETE WASHOUT** 

LIMIT OF DISTURBANCE

ITEM

SANITARY GRAVITY SEWER LINE, SIZE & FLOW DIRECTION

SANITARY SEWER FORCE MAIN, SIZE

SANITARY SEWER MANHOLE (S.M.H.)

WATER VALVE (W.V.) OR METER (W.M.)

STORM DRAIN MANHOLE (S.D.M.H.)

STORM DRAIN LINE (CMP OR RCP)

UTILITY POLE W/ OVERHEAD SERVICE

(TELEPHONE OR ELECTRIC OR BOTH)

UNDERGROUND ELECTRIC

JNDERGROUND TELEPHONI

PAVEMENT TO BE REMOVED

**CONCRETE CURB & GUTTER** 

NDIVIDUAL TREE OR BUSI

STRUCTURE (CONCRETE, WOOD,

EMBANKMENT SIDESLOPES (DOWN)

PROPERTY OR RIGHT-OF-WAY LINE

DRAINAGE DITCH OR SWALE

ELEVATION SPOT SHOT

CONSTRUCTION NOTE

BENCH MARK

CENTERLINE

LIGHT POLE

CHAINLINK FENCE

STOCKADE FENCE

CONCRETE SIDEWALK, SLAB / PAVING

IMPERVIOUS SURFACED ROAD, DRIVE

UNDERGROUND GAS MAIN

SANITARY SEWER CLEANOUT

SILT FENCE

& FLOW DIRECTION

WATER MAIN & SIZE

**CONCRETE MIXING OPERATION** 

# WESTERN

SUSSEX COUNTY, DE

G R O U

ARCHITECTURE

ENGINEERING

**Delaware** 

309 South Governors Avenue

Dover, DE 19904 302.734.7950

The Tower at STAR Campus

100 Discovery Boulevard, Suite 102

Newark, DE 19713

302.369.3700

Maryland

312 West Main Street, Suite 300

Salisbury, MD 21801

410.546.9100

North Carolina

3333 Jaeckle Drive, Suite 120

Wilmington, NC 28403

910.341.7600


www.beckermorgan.com


### **COVER SHEET &** | GENERAL NOTES


ISSUE BLOCK


6. 02-03-23 REVISED PER DNREC COMMENTS ISSUED ON 02-01-2023 12-16-22 REVISED PER SCD COMMENTS SSUED ON 12-07-2022 11-30-22 REVISED PER FIRE MARSHAL COMMENTS ISSUED ON 11-18-2022 3. 11-15-22 REVISED PER CITY OF SEAFORD COMMENTS ISSUED ON 10-11-2022 10-10-22 REVISED PER FIRE MARSHAL COMMENTS ISSUED ON 09-22-2022 10-07-22 REVISED PER SCD COMMENTS ISSUED ON 10-03-2022 MARK DATE

PROJECT NO.: 2021150.00 DATE: 09-12-2022 SCALE: DRAWN BY: A.C.F. PROJ. MGR.: J.D.R.











G R O U P

ARCHITECTURE





LANDSCAPE REQUIREMENTS:

TOTAL IMPROVED AREA: 9.62 AC.±

2. LANDSCAPING REQUIREMENTS:

1. ANY PART OR PORTION OF THE SITE WHICH IS NOT USED FOR BUILDINGS, OTHER STRUCTURES, LOADING OR PARKING SPACES AND AISLES, SIDEWALKS ARE DESIGNATED STORAGE AREAS SHALL BE PLANTED WITH AN ALL SEASON GROUND COVER AND SHALL BE LANDSCAPED WITH TREES AND SHRUBS IN ACCORDANCE WITH AN OVERALL LANDSCAPE PLAN AND SHALL AND IN KEEPING WITH NATURAL SURROUNDINGS.A REPLACEMENT PROGRAM NON-SURVIVING PLANTS SHOULD BE INCLUDED.

2. THE PLOT PLAN MUST SHOW A SATISFACTORY METHOD OF IRRIGATING ALL PLANTED AREAS. THIS MAY BE EITHER BY A PERMANENT WATER SYSTEM OR BY HOSE. ANY SINGLE PARKING AREA WITH FIFTY (50) OR MORE SPACES SHALL UTILIZE AT LEAST FIVE PERCENT (5%) OF ITS AREA IN LANDSCAPING, WHICH SHALL BE IN ADDITION TO OPEN AREA

. PROPOSED PLANTINGS PROVIDED : 33 TREES 195 SHRUBS

#### GENERAL LANDSCAPE NOTES

QUALITY AND SIZE OF PLANTS, SPREAD OF ROOTS, AND SIZE OF BALLS SHALL BE IN ACCORDANCE WITH THE CURRENT STANDARDS OF THE AMERICAN ASSOCIATION OF NURSERYMEN "AMERICAN STANDARDS FOR

REQUIREMENTS OF THE DISTRICT.

EVERGREEN TREES SHALL HAVE A FULL, WELL-BRANCHED, CONICAL FORM TYPICAL OF THE SPECIES.

ALL DECIDUOUS SHADE TREES SHALL BRANCH A MINIMUM OF 7'-0" ABOVE GROUND LEVEL. TREES SHALL BE PLANTED AND STAKED IN ACCORDANCE WITH THE DETAIL SHOWN.

PLANT MATERIALS DELIVERED TO THE SITE IN UNCOVERED TRUCKS WILL BE REJECTED.

UNACCEPTABLE PLANT MATERIALS: MATERIALS WHICH HAVE DAMAGED OR CROOKED LEADERS, DEFORMED GROWTH HABIT, ABRASIONS OF THE BARK, SUN SCALD, WINDBURN, DISFIGURING NOT COMPLETELY CALLUSED WILL BE REJECTED. IN ADDITION, TREES HAVING THEIR CENTRAL LEADERS HEADED BACK WILL ALSO BE REJECTED. PLANTS WITH LOOSE OR CRACKED ROOT BALL OR CONTAINERS WILL BE REJECTED.

ALL PLANTS SHALL BE PLANTED IN TOPSOIL THAT IS THOROUGHLY WATERED AND TAMPED AS BACKFILLING PROGRESSES. NOTHING BUT SUITABLE TOPSOIL, FREE OF DRY SOD, STIFF CLAY, LITTER, STONES IN EXCESS OF ONE (1) INCH DIAMETER, ETC. SHALL BE USED FOR PLANTING.

MULCH FOR PLANTING BEDS SHALL BE SHREDDED HARDWOOD BARK MULCH UNLESS OTHERWISE SPECIFIED ON THE PLANS AND SHALL HAVE NO LEAVES. YOUNG GREEN GROWTH, BRANCHES, TWIGS, GREATER IN DIAMETER OF ½", WEEDS, SHAVINGS OR FOREIGN MATERIAL SUCH AS STONES, ETC. SHALL BE MIXED WITH THE MULCH. ALL SHRUB MASSES SHALL BE PLANTED IN CONTINUOUS MULCHED BEDS WITH A LIGHTLY COMPACTED DEPTH OF THREE (3) INCHES. ALL CONTAINER PLANTS ARE TO HAVE ROOTS CUT ON FOUR SIDES AND/ OR SPREAD OUT IN NEW SOIL MIXTURE.

ALL AREAS NOT STABILIZED IN PAVING OR PLANT MATERIALS SHOULD BE SEEDED AND MULCHED. (SEE EROSION & SEDIMENT CONTROL PLAN AND NOTES.)

LANDSCAPE BEDS NOT DEFINED BY CURBS, SIDEWALKS, WALLS OR OTHER STRUCTURES SHALL BE ENCLOSED BY ALUMINUM EDGING UNLESS OTHERWISE INDICATED.

AREAS DISTURBED BY LANDSCAPE OPERATIONS SHALL BE GRADED TO MATCH EXISTING TOPSOIL AND SEED OR

CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO UTILITIES AND MAY MAKE MINOR ADJUSTMENTS IN SPACING AND/OR LOCATION OF PLANT MATERIALS. CONTACTOR TO VERIFY "AS BUILT" LOCATION OF ALL

NO PLANT, EXCEPT GROUNDCOVERS, SHALL BE WITHIN THREE (3) FEET FROM SIDEWALKS.

NO TREE SHALL BE PLANTED CLOSER THAN TEN (10) FEET FROM ANY STRUCTURE OR BUILDING.

9. NO TREE SHALL BE PLANTED WITHIN TEN (10) FEET OF UNDERGROUND UTILITIES OR FIRE HYDRANTS. IO. ONLY TREES THAT REACH A HEIGHT AND SIZE AT MATURITY OF SMALL TO MEDIUM SHALL BE PLANTED UNDER

POWER LINES. THE CONTRACTOR SHALL WATER ALL PLANTS THOROUGHLY TWICE DURING THE FIRST 24-HOUR PERIOD AFTER PLANTING, AND THEN WEEKLY OR MORE OFTEN, IF NECESSARY, DURING THE FIRST GROWING SEASON,

UNLESS THE OWNER AGREES TO MAINTAIN AND WATER THEM. 12. TREES TO REMAIN ON-SITE SHALL BE PROTECTED WITH SNOW FENCE DURING CONSTRUCTION (SEE DETAIL).

THE PLANTING PLAN SHALL TAKE PRECEDENCE OVER THE PLANT SCHEDULE SHOULD ANY PLANT QUANTITY

DISCREPANCIES OCCUR.

NO SUBSTITUTIONS SHALL BE MADE WITHOUT APPROVAL OF THE OWNER AND/ OR THE LANDSCAPE ARCHITECT

ALL NEW TREES SHALL BE GUARANTEED TO SURVIVE FOR ONE FULL YEAR AFTER INSTALLATION (FULL COST) ALL STAKES AND GUYS SHALL BE REMOVED FROM TREES AND SITE AS EARLY AS THREE (3) MONTHS, BUT NO LONGER THAN ONE (1) YEAR AFTER PLANTING.

#### **GENERAL IRRIGATION NOTES:**

MULCH: AFTER COMPLETION OF ALL PLANTING, ALL IRRIGATED NON-TURF AREAS SHALL BE COVERED WITH A MINIMUM LAYER OF FOUR (4) INCHES OF MULCH TO RETAIN WATER, INHIBIT WEED GROWTH AND MODERATE SOIL TEMPERATURE. NON-POROUS MATERIAL SHALL NOT BE PLACED UNDER THE MULCH.

LANDSCAPE WATER METER: A WATER METER AND BACKFLOW PREVENTION ASSEMBLY THAT ARE IN COMPLIANCE WITH STATE CODE SHALL BE INSTALLED FOR LANDSCAPE IRRIGATION SYSTEMS, AND THE LANDSCAPE WATER METER AND BACKFLOW PREVENTION ASSEMBLY SHALL BE SEPARATE FROM THE WATER METER AND BACKFLOW PREVENTION ASSEMBLY INSTALLED FOR INDOOR USES. THE SIZE OF THE METER SHALL BE DETERMINED BASED ON IRRIGATION DEMAND

PRESSURE REGULATION: A PRESSURE REGULATING VALVE SHALL BE INSTALLED AND MAINTAINED BY THE CONSUMER IF THE STATIC SERVICE PRESSURE EXCEEDS 80 POUNDS PER SQUARE INCH (PSI). THE PRESSURE-REGULATING VALVE SHALL BE LOCATED BETWEEN THE LANDSCAPE WATER METER AND THE FIRST POINT OF WATER USE, OR FIRST POINT OF DIVISION IN THE PIPE, AND SHALL BE SET AT THE MANUFACTURER'S RECOMMENDED PRESSURE FOR SPRINKLERS.

AUTOMATIC CONTROLLER: ALL IRRIGATION SYSTEMS SHALL INCLUDE AN ELECTRIC AUTOMATIC CONTROLLER WITH MULTIPLE PROGRAM AND MULTIPLE REPEAT CYCLE CAPABILITIES AND A FLEXIBLE CALENDAR PROGRAM.

ON SLOPES EXCEEDING 30%, THE IRRIGATION SYSTEM SHALL CONSIST OF DRIP EMITTERS, BUBBLERS, OR SPRINKLERS WITH A MAXIMUM PRECIPITATION RATE OF 0.85 INCHES PER HOUR AND ADJUSTED SPRINKLER

EACH VALVE SHALL IRRIGATE A LANDSCAPE WITH SIMILAR SITE, SLOPE AND SOIL CONDITIONS AND PLANT MATERIALS WITH SIMILAR WATERING NEEDS. TURF AND NON-TURF AREAS SHALL BE IRRIGATED ON SEPARATE

DRIP EMITTERS OR A BUBBLER SHALL BE PROVIDED FOR EACH TREE WHERE PRACTICABLE. BUBBLERS SHALL NOT EXCEED 1.5 GALLONS PER MINUTE PER DEVICE. BUBBLERS FOR TREES SHALL BE ON SEPARATE VALVE UNLESS SPECIFICALLY NOTED.

SPRINKLERS SHALL HAVE MATCHED PRECIPITATION RATE WITH EACH CONTROL VALVE CIRCUIT.

ALL CONTROLLERS SHALL BE EQUIPPED WITH AN AUTOMATIC RAIN SHUT-OFF DEVICE.

CHECK VALVES SHALL BE REQUIRED WHERE ELEVATION DIFFERENCES WILL CAUSE LOW-HEAD DRAINAGE. PRESSURE COMPENSATING VALVES AND SPRINKLERS SHALL BE REQUIRED WHERE A SIGNIFICANT VARIATION IN WATER PRESSURE WILL OCCUR WITHIN THE IRRIGATION SYSTEM DUE TO ELEVATION DIFFERENCES.

DRIP IRRIGATION LINES SHALL BE PLACED UNDERGROUND OR OTHERWISE PERMANENTLY COVERED, EXCEPT FOR DRIP EMITTERS AND WHERE APPROVED AS A TEMPORARY INSTALLATION. FILTERS AND END FLUSH VALVES SHALL BE PROVIDED AS NECESSARY.

IRRIGATION ZONES WITH OVERHEAD SPRAY OR STREAM SPRINKLERS SHALL BE DESIGNED TO OPERATE BETWEEN 6:00 P.M. AND 10:00 A.M. TO REDUCE WATER LOSS FROM WIND AND EVAPORATION. THIS WOULD EXCLUDE DRIP OR BUBBLER ZONES.

PROGRAM VALVES FOR MULTIPLE REPEAT CYCLES WHERE NECESSARY TO REDUCE RUNOFF, PARTICULARLY SLOPES AND SOILS WITH SLOW INFILTRATION RATES.

#### DELAWARE LANDSCAPE ARCHITECTS CERTIFICATION

CHAD D. CARTER, RLA, ASLA, HEREBY CERTIFY THAT I AM A LANDSCAPE ARCHITECT IN THE STATE OF DELAWARE, THAT THE LANDSCAPING INFORMATION SHOWN HEREON HAS BEEN PREPARED UNDER MY SUPERVISION AND TO MY BEST KNOWLEDGE AND BELIEF, REPRESENTS GOOD LANDSCAPING PRACTICES.

BMG NO.: L-04

**DECIDUOUS TREE PLANTING DETAIL** 

CHAD D. CARTER, RLA 02-03-2023 CHAD D. CARTER, RLA, ASLA DATE



309 South Governors Avenue Dover, DE 19904 302.734.7950

The Tower at STAR Campus 100 Discovery Boulevard, Suite 102 Newark, DE 19713 302.369.3700 Maryland

312 West Main Street, Suite 300 Salisbury, MD 21801

410.546.9100 North Carolina 3333 Jaeckle Drive, Suite 120

Wilmington, NC 28403 910.341.7600

www.beckermorgan.com




PROJECT TITLE

#### **WESTERN SUSSEX BUSINESS CAMPUS**

**CITY OF SEAFORD** SUSSEX COUNTY, DE

SHEET TITLE

LANDSCAPE PLAN



SSUE BLOCK 6. 02-03-23 REVISED PER DNREC COMMENTS ISSUED ON 02-01-2023 12-16-22 REVISED PER SCD COMMENTS 12-16-22 ISSUED ON 12-07-2022 11-30-22 REVISED PER FIRE MARSHAL COMMENTS ISSUED ON 11-18-202

3. | 11-15-22 | REVISED PER CITY OF SEAFORD 2. | 10-10-22 | REVISED PER FIRE MARSHAL COMMENTS ISSUED ON 09-22-202 REVISED PER SCD COMMENTS ISSUED ON 10-03-2022

MARK DATE DESCRIPTION PROJECT NO.: 2021150.00 DATE: 09-12-2022 SCALE:

F:\AutoCAD\Projects\2021\2021150\DWG\2021150-SITE-C3D21-DE.dwg, Feb 03, 2023 - 12:18pr

1" = 50' DRAWN BY: A.C.F. PROJ. MGR.: J.D.R SHEET